



# TUCKER-KIRBY CO.

March, 2009

We have roots where others have branches!

## Project: Restaurant Depot in Charlotte, NC

<b>Size:</b>	54,600 sq. ft.		
<b>Construction Start:</b>	07/08	<b>Completion:</b>	02/09
<b>Scope of Work:</b>	Foundations, SOG, 47 panels, 1,000 sf paving, walks, electrical & chiller pads, ~600 lf CIP walls		
<b>Challenges of Project:</b>	8" of rain between mid-November 08 & early January 09		

<b>Tilt Wall Contractor:</b>	Seretta Construction
<b>Products:</b>	Spec Tilt W/B, Foamular, Greenstreak Formliner & Shim Paks & Reveal Stix, Dayton Superior T-110 Lift System
<b>Supplied By:</b>	Tucker-Kirby Company Charlotte, NC office
<b>Special Features:</b>	Brick formliner used on 8 full panels Insulated SOG in freezer area (6,800 sf)



Website: <http://www.TuckerKirby.com>